

CAUVERY NEERAVARI NIGAM LIMITED

(A Government of Karnataka Undertaking)

Registered Office: Cauvery Bhavan, Kempe Gowda Road, Bengaluru 560 009

Divisional Office: Mysuru Irrigation Division, No. 14, KRS Road, Mysuru 570 010

NOTICE INVITING TENDER (e-NIT)

NIT No.: CNNL/MYS-DIV/DS/2026-27/007

Date: 10 June 2026

TENDER FOR DESILTING OF VISVESVARAYA CANAL MYSURU REACH (PACKAGE DS-07)

Chainage: Km 96.400 to Km 110.700 (14.3 km)

1. WORK DETAILS

Cauvery Neeravari Nigam Limited (CNNL), Mysuru Irrigation Division, invites online tenders from eligible contractors for the following work:

Work Name : Desilting of Visvesvaraya Canal (Mysuru Reach), Package DS-07
Location : Chainage Km 96.400 to Km 110.700, Mysuru District, Karnataka
Scope : Mechanical and manual desilting of the main canal bed and banks, disposal of silt, restoration of embankment slopes (1:1.5), repair and re-plastering of CC lining (grade M15) at 23 locations, reconstruction of 4 cross-drainage structures (sluice type), vegetation clearance on canal banks (both sides, 14.3 km), and desilting of 6 field channels (each 0.8 1.4 km).

Estimated Cost : Rs. 4,10,00,000/- (Rs. Four Crore Ten Lakh)
EMD : Rs. 82,000/- (Rs. Eighty-Two Thousand) 2% of estimated cost
Tender Fee : Rs. 2,000/- (non-refundable, paid online)
Performance Security : 5% of accepted contract value
Defect Liability Period : 12 months from date of substantial completion

2. IMPORTANT DATES

Publication of e-NIT : 10 June 2026
Last date for document download : 05 July 2026, 17:30 hrs
Last date for clarifications : 08 July 2026
Pre-Bid Meeting : 10 July 2026, 11:00 hrs at CNNL Mysuru Divisional Office
Last date for bid submission : 22 July 2026, 17:00 hrs
Opening of Technical Bids : 24 July 2026, 11:00 hrs
Bid validity : 120 days from date of submission

Bids must be submitted online on the Karnataka e-Procurement portal (<https://eproc.karnataka.gov.in>). Physical submission not accepted.

3. SCOPE OF WORK DETAIL

3.1 Canal Desilting

The accumulated silt, organic debris, and weed growth in the canal bed and banks shall be removed using the following methods:

- (a) Mechanical desilting using excavator + tipper (for main canal bed)
 - (b) Manual desilting and basket removal (for reaches inaccessible to machinery)
- Excavated silt to be disposed at designated spoil sites approved by CNNL.

3.2 Embankment Restoration

Embankment cross-sections shall be restored to design dimensions (FSL, bank width 2.4 m, side slope 1:1.5). Settlement or erosion pockets to be made good with compacted earth (proctor density 95%).

3.3 Concrete Lining Repair

Existing M15 CC lining to be repaired at 23 damaged locations (total area approx. 1,850 sqm). Repair shall include:

- (a) Removing loose/cracked panels
- (b) Sub-grade compaction
- (c) Providing 75 mm M15 CC lining with 3 mm plaster finish
- (d) Expansion joints with bitumen felt at 6 m centres

3.4 Cross-Drainage Structures

Reconstruction of 4 cross-drainage sluices (rectangular box type, 0.6 m opening, head wall and tail wall in M20 CC, wooden shutters). Co-ordination with CNNL's hydraulic engineer for gate setting.

3.5 Field Channel Desilting

Manual desilting of 6 field channels (total 6.2 km). Silt disposal at farmer's field or spoil site as directed by field engineer.

=====

4. ELIGIBILITY CRITERIA

=====

IMPORTANT: Bids from contractors not meeting ALL the eligibility criteria listed below will be summarily rejected at the technical evaluation stage. Waivers will not be granted.

4.1 Annual Turnover

The bidder shall have an Average Annual Turnover not less than Rs. 2.00 Crore from civil or irrigation works during the last 3 (three) financial years (2023-24, 2024-25, 2025-26).

Supporting documents: Audited Profit & Loss Statement and Balance Sheet for last 3 financial years, certified by a Chartered Accountant.

4.2 Technical Experience Similar Canal / Irrigation Works

The bidder shall have successfully completed at least 1 (one) similar canal work or irrigation scheme work during the last 5 (five) years (on or after 01 April 2021), of value not less than Rs. 1.50 Crore.

"Similar work" means: Desilting, embankment repair, or canal lining work on an irrigation canal, distributary, or field channel maintained by an Irrigation Department, CNNL, KNNL, CADA, or equivalent organisation.

Works involving road embankments, building construction, or drainage of non-irrigation structures shall NOT qualify as similar work for this purpose.

Supporting documents: Work order + Performance / Completion certificate from the concerned Irrigation Department or parastatal, specifying the nature, value, and date of completion of the work.

4.3 Contractor Registration

The bidder shall hold a valid registration as Class II Contractor or above (Class I, Special Class) with:

- (a) Karnataka Public Works Department (KPWD), OR
- (b) Karnataka Rural Infrastructure Development Limited (KRIDL), OR
- (c) CNNL / KNNL (irrigation department registration), OR
- (d) Central Water Commission (CWC) / CPWD equivalent category

A road-only PWD registration without an irrigation/hydraulic works endorsement does not satisfy this condition.

4.4 Other Documents Required

- (a) Valid GST Registration (GSTIN)
- (b) PAN
- (c) EPF / ESIC Registration
- (d) Undertaking that no litigation / arbitration is pending with any Irrigation Department in Karnataka

5. EVALUATION CRITERIA

5.1 Technical bids will be evaluated on pass/fail basis against Section 4.

Only technically qualified bidders will proceed to financial bid opening.

5.2 Financial bids will be evaluated on L1 (lowest valid bid) basis.

Bids above 10% of estimated cost shall not be considered for award.

5.3 CNNL reserves the right to award work to L2 if L1 fails to execute the agreement within 7 working days of letter of award.

6. SITE CONDITIONS

6.1 Canal water shall be shut down for the work season (1 October to 31 March).

All desilting work must be completed within this window.

6.2 Contractors must arrange own water supply for curing of concrete works.
No potable water supply from CNNL will be provided.

6.3 Machinery mobilisation: access roads to the canal bank are kachcha (unpaved) and may require minor repair for heavy vehicles. Contractor to include mobilisation cost in their rates.

6.4 The canal traverses agricultural land. Contractors must coordinate with CNNL Field Engineer to minimise crop damage. Any crop damage compensation is the contractor's liability.

=====

7. GENERAL TERMS

=====

7.1 All works to be executed as per KPWD Specifications for Irrigation Works (2018 edition) and IS codes as applicable.

7.2 CNNL's Engineer-in-Charge's decision on quality and measurement is final.

7.3 Subletting of work (in full or in part) is not permitted.

7.4 The successful bidder must deploy a resident site engineer (Diploma in Civil Engineering, minimum 3 years irrigation works experience).

7.5 CNNL reserves the right to cancel or postpone the tender at any stage without assigning any reason.

7.6 Disputes are subject to jurisdiction of courts in Mysuru District.

=====

8. CONTACT

=====

Divisional Engineer (Canals)
CNNL Mysuru Irrigation Division
No. 14, KRS Road, Mysuru 570 010
Email: de-canal.mys@cnnl.karnataka.gov.in
Phone: 0821-2440-122

=====

END OF NOTICE INVITING TENDER
NIT No.: CNNL/MYS-DIV/DS/2026-27/007

=====